# Hwy 101/61 Flood Mitigation Past, Present, and Future

Presented by: Nicole Bartelt Minnesota DOT







#### Area of Concern: SW Metro



#### Area of Concern: SW Metro



## SW Metro Flooding Snapshot

- 50,000+ vehicle per day detoured. 20,000 commuters.
- Regional and local impact.
- Significant economic impact.
- Emergency response time compromised.



Friday, October 1, 2010 6:30 a.m.

CH 18, ½ mile south of TH 169 interchange



# TH101 & TH41 MnDOT Flood Impact Study







## Project Background



## Study Components

- Analysis of historical flooding
- Development and Evaluation of alternatives
- River modeling
- Agency involvement
  - USFWS
  - DNR
  - MPCA
  - USACE

Watershed Management Organization

## Flooding History – TH41



# Spring 2011 Flood – TH41 Looking North Towards Chaska



## Flooding History – TH101



# Spring 2011 Flood – TH101 Looking North Towards Chanhassen



#### Hydraulic Modeling Objectives

- Assess Water Surface Elevation for Existing Conditions
  - Existing Conditions Model Approx. 35 miles
  - From Carver to confluence with Mississippi River
     HEC-RAS 4.1.0
- Develop a Calibrated 2-D Model
  - Finite-Element Surface-Water Modeling System (FESWMS by Baird)
- Assess Impact of Design Alternatives
  - Reduce Road Closure Frequency & Duration

## Hydraulic Models

- HEC-RAS (1D) vs. FESWMS (2D)
   HEC-RAS
  - Basic model used to evaluate alternatives
  - Regulatory model Calibrated by USACE
  - FESWMS
    - Detailed data set (river cross sections, USACE hydrographic survey, LiDAR data, and USDA/NRCS National Elevation Data)
    - More accurately evaluates velocities
  - D/S boundary condition: USGS Gage at Ft. Snelling
    Flow values: USGS Gage near Jordan

## 1D vs 2D Finite Element Grid - TH41



## Finite Element Grid Near TH101



### **2-D Model Calibration**

- Hydrodynamic Modeling using FESWMS
  - Calibrated Using Field Data
    - March 28, 2011 Event
    - Approximate 30-yr Event
    - Compared Flooded Inundation Area from Model to Actual Flood Photos
    - Measured Flow, Water Surface Elevation, and Velocity

## 2011 Flood Event – TH41



## 2011 Flood Event – TH101



# Flow at Bridge 10012, TH41



#### Why Not Just Raise The Road

- Raising the road would cause impacts upstream as the flow is restricted due to a higher embankment
- Floodplain regulations do not allow fill in the floodway that will cause the river to rise
- Need "no-rise" solution

#### **Design** Alternatives

- Filling to Raise Road Profile
  - Modeling Showed Surcharge (Rise) in 100-Yr Floodway WSE
  - Culverts Could Not Mitigate Surcharge
- Use of Upstream Storage
   Not Feasible Due to Flat River Profile
- LOMR to Allow for Some Stage Increase
  - Not Practical Due to Length of Upstream Impact (30+miles)
- Land Bridge / Bridge

# Land Bridge Design

- Iterative Process which Involved Varying:
  - Road Elevation
  - Bridge Length
  - Pier Width

- Pier Spacing
- Bridge Deck Depth



## **TH41 Preferred Concept**



## Road Closure Frequency – TH41



#### Road Closure Duration – TH41



#### **TH101 Preferred Concept**



## Road Closure Frequency – TH101



#### Road Closure Duration – TH101

![](_page_27_Figure_1.jpeg)

## Modeling Results

- TH 41 and TH 101
  - No increase in stage (No Rise)
- TH 41
  - Velocity decreased for 10-Year event
  - Increased for larger events, yet less than maximum velocity for existing conditions
- TH 101
  - Velocity decreased for all events

## **Evaluation Criteria**

- Construction Cost
- Benefit Cost
- Property Impacts and Costs
- Constructability
- Environmental Impacts/Opportunities
- Community Input

#### **Comparison and Selection of Alternatives**

• TH41 Preferred Concept

- \$22.4 Million to Design & Construct
- Benefit/Cost = 3.06
- TH101 Preferred Concept
  - \$33.3 Million to Design & Construct
  - Benefit/Cost = 3.81
- TH101 Selected
  - Carries more traffic
  - Reduced closure frequency and duration

![](_page_31_Picture_0.jpeg)

#### **Project Partners:**

![](_page_31_Picture_2.jpeg)

![](_page_31_Picture_3.jpeg)

![](_page_31_Picture_4.jpeg)

![](_page_31_Picture_5.jpeg)

![](_page_31_Picture_6.jpeg)

![](_page_31_Picture_7.jpeg)

# Hwy 101/61 Aerial Photo

![](_page_32_Picture_1.jpeg)

Picture courtesy of Tony Wotzka, MnDOT

# Hwy 101/61 Aerial View of Flooding

![](_page_33_Picture_1.jpeg)

Photo courtesty of SRF, Inc

#### Project Background

- Flood Mitigation Study Completed in 2011
- Applied for Flood Mitigation Bonds in February 2012.
- March 2012: Awarded \$20,000,000 for 2 lane bridge.
- Counties Requested 2012 Legislature to fund -4-lane.
- January 2013: Cooperative Project started

## **Combined Project**

![](_page_35_Picture_1.jpeg)

- 4226' 4 lane Bridge offset from existing 101 roadway.
- 4-lane CR 61 (Flying Cloud Drive) with Roundabouts.
   <sub>39</sub>Signalized Intersection at 101N.

## Floodplain Bridge

![](_page_36_Figure_1.jpeg)

# Floodplain Bridge Visualization

![](_page_37_Picture_1.jpeg)

APRIL 13 196 HIGH WATEF ELEVATION

## Engineering & Environmental Challenges

- Soil/foundation stability.
   Organics 15'-90' deep.
- Contaminated Soils.
- Bluff Creek Realignment.
- Water Quality Treatment.
- Cultural Resources.

## Soil/Foundation stability

- Extended bridge ~1200ft to the north
- Pile bent pier design lateral stability
- Other soil stability measures
  - Pile supported embankment
  - Geofoam
  - Significant Muck removal and granular fill

#### Bluff Creek Realignment

- Extended bridge ~1200ft to the north
   Remove box culverts under Hwy 101
- Meandering channel pattern

![](_page_40_Picture_3.jpeg)

#### Water Quality Treatment

- Overall Environmental Benefit
  - Removing Hwy 101 causeway, reconnecting floodplain
- Significant Resource Agency involvement

![](_page_41_Figure_4.jpeg)

## Cultural Resources - Archaeology

![](_page_42_Picture_1.jpeg)

## Cultural Resources - Archaeology

![](_page_43_Picture_1.jpeg)

Pictures courtesy of Frank Florin

## Other Challenges

- Funding
- Schedule
  - MnDOT has committed to building bridge in 2014.
  - Risk with combining bridge and 'Y' projects.
- Construction Phasing
- Roles and Responsibilities
- →Outlined in Construction Agreement

## Project Update

- Project Awarded on May 20, 2014 to Ames Construction.
  - Winning Bid was \$49.3M
  - Engineers Estimate was \$50.4M
- Project Groundbreaking on June 24, 2014

![](_page_45_Picture_5.jpeg)

## Project Update

- PROJECT START DELAYED DUE TO FLOODING!
- Actual project start in Late July 2014
- Anticipated completion in November 2015

#### Twitter: @SWReconnectProj

Facebook: https://www.facebook.com/SouthwestReconnection Project

http://www.dot.state.mn.us/metro/projects/hwy101ri ver/

![](_page_47_Picture_0.jpeg)

# Acknowledgements

Lyndon Robjent, Carver County Molly Kline, MnDOT Ron Leaf, SEH Brad Woznak, SEH Rachel Pichelmann, SEH

![](_page_47_Picture_3.jpeg)

![](_page_47_Picture_4.jpeg)

![](_page_47_Picture_5.jpeg)